


BID QUESTIONS AND ANSWERS TURBERVILLE ROAD BRIDGE REPLACEMENT OVER WRIGHTS CREEK

12/08/2025

1. Plans call for Jetted Piles but state "no jetting without Engineer approval"
RESPONSE: Based on geotechnical recommendations the piles shall be jetted. Approval by the Engineer will not be necessary since this is a requirement.
2. Test piles - lengths in table show 92 LF but qty shows 100 LF
RESPONSE: 124 LF of Test Pile is required. $(47 \text{ LF} + 15 \text{ LF}) * 2 \text{ Test Piles} = 124 \text{ LF}$
There will be one Test Pile at each abutment. Plans will be updated to reflect.
3. Can Geotechnical Report be provided?
RESPONSE: Yes, A PDF of Geotechnical report was sent out via email on 11/5/2025.
4. Verify quantity for Test Pile and Production Piles
RESPONSE: Pay Item 455-143-2 Test Piles Prestressed Concrete 14" SQ = 124 LF
Production Piles 455-34-2 Prestressed Concrete 14" SQ Pay Item quantity was checked and verified. Quantity is correct at 776 LF.
5. Are there any available standard plans for Baily Bridge.
RESPONSE: Yes, A PDF of a Standard Plans for a Baily Bridge used as a reference for the design of the sub structure will be provided for contractor's reference and use.
6. Is there an official addendum to acknowledge for the information and revisions provided on 11/17/25?
RESPONSE: Yes, Addendum one memo was sent out 11/25/2025 addressing the information and revisions provided via email on 11/17/2025.
7. Will you provide plans and a parts list for what is included in the Bailey Bridge System provided by the County?
RESPONSE: A PDF file of Baily Bridge Standard Plans utilized for the sub structure design was provided as a separate PDF for reference. The County does not have a parts list assembled for the Baily Bridge System to be provided.
8. Given the Thanksgiving Holiday and planned time off, will the County consider a bid date extension?
RESPONSE: The County has approved a bid date extension. See Addendum 2 emailed out on 11/25/2025.



9. Plan sheet 5&6 have notes that the existing end walls and rip rap remain. Plan sheet 7 calls for the existing end walls to be removed. What is the intent on this?

RESPONSE: The intent is for the existing end walls and rip rap to be removed. This will be updated in a plan revision after bid to be clearer.

This Question and Answer now becomes a part of the original Bid Documents.