


SEAL

EB 0008794

BIDDING DOCUMENTS

SCALE



REVISIONS

NO.	DESCRIPTION	DATE

NO. DESCRIPTION DATE

DRAWN BY: BTW

APPROVED BY: BTW

CHECKED BY: CLK

DATE: DECEMBER 2023

TITLE

**OVERALL SITE
 UTILITY PLAN**

PROJECT NO. 50136796

C5.1

SHEET NO.



EXIST. FIRE HYDRANT

EXIST. 6" PVC WATERMAIN

INSTALL 4" TAPPING SADDLE AND VALVE WITH BOX ON EXIST. 6" PVC WM

EXIST. 6" PVC WATERMAIN

CONST. 804 LF 4" C-900 PVC WATERMAIN TO BUILDING PROVIDE 10' SEPARATION FROM EXIST. PVC FORCEMAIN FROM EMS PUMP STATION

CUT AND PATCH SIDEWALK CROSSING

CUT AND PATCH DRIVEWAY CROSSING

USE 4" 45 MJ BEND TYP.

PROPOSED 2" FM FROM BUILDING OPEN CUT AND PATCHED

INSTALL 4" VALVE AND 4X2 REDUCER AT ENTRANCE TO BLDG

ZONE "A"
 ZONE "X"

WETLAND LINE

SWMF-1